BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate

Name of Work: Maintenance And Repair of Burial Grounds in Ward No. 10 (Doddabommasandra).

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	432.00	KSRB 2-2.4:Earth work for lowering and levelling the ground other than foundation works by mechanical means upto 3.00 depth, including providing shoring strutting and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, filling back the excavated earth to the extent required & utilising/transporting the remaining earth upto 1.00 km lead. Including the cost of labour & HOM as per drawing and	Cum	135.68	Rupees One Hundred Thirty Five and Sixty Eight Paise Only
2	77.58	KSRB 2-2.1:: Earthwork excavation for foundationof buildings, water supply and sanitary lines and electrical conduitsetc, either in pits or in trenches 1.5m and above in width, in soil notexceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of	Cum	317.12	Rupees Three Hundred Seventeen and Twelve Paise Only
3	27.76	KSRB 4-1.2 : Providing and laying in position plain cement concreteof Mix 1:4:8 with OPC @ 220kgs, with 40mm and down size gradedgranite metal coarse aggregates @0.892cum and fine aggregates @0.465cum machine mixed, machine mixed, concrete laid in layers notexceeding 15 cms. thick, well compacted, in foundation, including costof all materials, labour, HOM curing complete as per specifications.Specification No. KBS 4.1, 4.2 (pg No.13.I.No.4.2)	Cum	5609.52	Rupees Five Thousand Six Hundred Nine and Fifty Two Paise Only
4	23.81	KSRB 5.2-3 : - Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammered dressed in courses not less than 20 cms high, bond stones at 2m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13 (P.No.25- I.No.5.6)	Cum	4963.68	Rupees Four Thousand Nine Hundred Sixty Three and Sixty Eight Paise Only
5	24.42	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth cills and string courses cost of all	Sqm	386.64	Rupees Three Hundred Eighty Six and Sixty Four Paise Only
6	3.36	KSRB 4-6.5 : Providing and removing centering, shuttering, strutting,propping etc., and removal of form work for columns, pillars, postand struts, square / rectangular/ polygon in plan including cost of allmaterials, labour complete as per specifications.Specification No. KBS 4.6.2 (P.No.16 - I.No.4.32)	Sqm	492.48	Rupees Four Hundred Ninety Two and Forty Eight Paise Only
7	5.14	KSRB 4.2.1 : Providing and laying in position reinforced cement concrete of Design Mix M25 with OPC @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.70 cum and fine aggregtes @ 0.47cum, with super plasticisers @ 3 liters confirming to IS 9103-1999 reafirmed-2008 at machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings, pedastals, retaining walls, return walls, walls (any thickness) including attached pilasters,columns, pillars,posts,struts,buttresses,bed blocks, anchor blocks & plinths etc., including cost of all materials, labour, HOM curing, complete but excluding cost of	Cum	6276.96	Rupees Six Thousand Two Hundred Seventy Six and Ninety Six Paise Only

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
8	0.51	KSRB M2200-6 Providing T.M.T bars Fe 550 steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost	Tonne	74316.96	Rupees Seventy Four Thousand Three Hundred Sixteen and Ninety Six Paise Only
9	73.26	KSRB 5-14: Providing and constructing load bearing wall with solid concrete blocks having block density not less than 1800kg/m3 having a minimum average compressive strength of 4.00 N/mm2 confirming to IS 2185 (Part 1):2005 and constructed with CM 1:4, as per IS 2572:2005 including cost of all materials labour charges, scaffolding, curing, hire charges of machineries etc., complete as per specifications. blocks of size 400x200x200mm KBS No.5.4 (P.No-27,I No-5.26.1)	Sqm	962.00	Rupees Nine Hundred Sixty Two Only
10	475.44	KSRB15-3.8 : Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. (P.No-116,I No-	Sqm	281.88	Rupees Two Hundred Eighty One and Eighty Eight Paise Only
11	475.44	KSRB 15-16.1 : Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to give an even shade after throughly brooming the	Sqm	110.16	Rupees One Hundred Ten and Sixteen Paise Only
12	10.50	Providing and fixing M.S. Gate as per Chief Architect Drawing, using 50mm x 50mm 14 guage M.S. hollow pipe frame work bent to ornamental shape as shown in the drawing and 35mm x	Sqm	3252.96	Rupees Three Thousand Two Hundred Fifty Two and
13	21.00	KSRB 15-18.2 : Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials,	Sqm	102.60	Rupees One Hundred Two and Sixty Paise Only
14	15.60	Cement concrete pavement.Construction of un-reinforced plain cement concrete pavement, using a grade concrete M30 over a prepared base with OPC coarse aggregate @ 0.69cum fine aggregate @ 0.46cum,coarse and fine aggregate confirming to IS:383-2016,with superplastisiser @3lts confirming to IS9103-2008mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing). Spreading the concrete with shovels, rackers compacted using needle, screed and plate vibrator and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints including groove cutting charges, joint filler, separation membrane, selant primer, joint sealant, admixtures as approved, curing compound, finishing to lines and grades, textured with texturing machine,and curing including cost of all	Cum	5210.96	Rupees Five Thousand Two Hundred Ten and Ninety Six Paise Only
15	14.70	Providing and Fixing pre cast covering Slab 250mm thick made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work,curing,including cost of alll materials, labour,hire charges of machinery, loading, unloading, lead and lift,transportation etc ,complete.As per Engineer incharge	Sqm	5418.00	Rupees Five Thousand Four Hundred Eighteen Only

"NO OF CORRECTION NIL"
"DTS APPROVED"

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

Note:

1 Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)

2 Unit rates and prices shall be quoted by the Tender in Indian rupees.

3 Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)

4 Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))